

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 10 W.

\_\_\_\_\_ Twp \_\_\_\_\_

\_\_\_\_\_ COUNTY

DESCRIPTION OF CORNER \_\_\_\_\_ Meander Corner between Sec.'s 3-4 on shore of Lake Superior

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER \_\_\_\_\_ Witness marked by Lawrence:  
16" W. Birch \_\_\_\_\_ S 5° E 130 links  
"S 3 NBT"

New Witness: 8" Red Pine \_\_\_\_\_ N 65° E 126 1/2 links  
"M.C. NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced M.C. from one probable white birch B.T. bearing S 10° W 116 links.

Found post on ground set by H. Lawrence, Reg. Surveyor, in 1936.

Checked distance south 4.76 chs. to 1/4 corner between 3-4.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 6/12/57  
REGISTERED LAND SURVEYOR