

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48-49 NR. 10 W.

Luce

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 2-3-34-35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 7" Tamarack S 54° E 75½ links

"S 2 NBT"

10" W. Pine N 28° W 153½ links

"S 34 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner from one spruce B.T. bearing S 66° E 16 links.
B.T. in excellent condition.

Distance south to pond 1 ch.

Corner lies 1½ chs. south of swamp edge and in wet marsh.

Corner perpetuated by Jim Cook, surveyor, in 1936.

Shown to us by B. McTiver, District Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 6/12/57
REGISTERED LAND SURVEYOR