

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49.. NR.. 10 W..

Luce

..... COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 34-35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" W. Pine S 73° W 13 links

10" W. Pine N 55° E 26 links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner as set by T. J. McLaren, McMillan.

Checked with original line tree 8.65 chs. south and 10.33 chs. north.

Gov't chainage longer than present day chainage. Post set proportionate distance between line trees.

Noted bearing trees as marked by McLaren.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/12/57
REGISTERED LAND SURVEYOR