

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 48-49 NR 10 W

----- Luce ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 35-2 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 12" Hemlock ----- N 59° E ----- 78 links -----
----- "1/4 S NBT" -----

12" Hemlock ----- S 52° W ----- 62 links -----
----- "1/4 S NBT" -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from one hemlock B.T. bearing N 27° W 17 links.
B.T. has been cut, part of face and notch remains.

Cedar post in place.

Shown to us by B. McTiver, District Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/12/57
REGISTERED LAND SURVEYOR