

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 10 W.

Ince COUNTY

DESCRIPTION OF CORNER Meander corner between Sec.'s 2-3 on shore of Lake Superior

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" Twin Red Pine S 32° W 61 links
"W.C. BT"
10" Red Pine S 13° E 103 links
"W.C. BT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Placed witness corner 2.50 chs. south of position of meander corner.

Established this witness corner by chaining and extending section line from 1/4 corner between Sec.'s 2-3 7.50 chs. south of here.

Gov't chainage = 10.00 chs. from 1/4 corner to meander corner.

Considerable erosion along lake shore.

Placed corner with B. McTiver, District Forester and Lawrence Rubick, Forestry Aide.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 6/13/52
REGISTERED LAND SURVEYOR