

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. 2 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>X</u> S. R. <u>10</u> E. <u>X</u> W.	<u>H-9, I-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-15, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-9** Quarter Corner between Section's 22-27, set by Geo. H. Cannon D.S. in 1854.
Bearings were: Beech 10, N30°W, 43 lks. and Beech 10, S28°E, 38 lks.
- I-11** Section Corner common to Sec's 26-27-34-35, set by Geo. H. Cannon D.S. in 1854.
Bearings were: Balsam 10, S15°E, 25 lks. and Balsam 10, N40°W, 35 lks.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-9** Corner restored midway and on line between two Section Corners.
- I-11** Corner restored at wood post found by survey crew. Distance to corners North and West check well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at both corners.
- H-9** New Bearings: 18" W. Pine, S89°W, 22.3' and 16" W. Pine, S2°W, 44.1' and 12" W. Pine, S26°E, 43.2'.
 - I-11** New Bearings: 24" W. Pine, N73°W, 38.2' and 10" W. Pine, S64°E, 14.2' and 12" W. Pine, S39°W, 38.3'

SIGNED BY Billy D. Buckler DATE 9-8-78
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____