

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 10 E. W.	C-4
2. PROPERTY CONTROLLING IN SECTION	8 T. 49 N. R. 10 E. W.	3-Sec. 8, 1-Sec. 8 4-Sec. 8
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-20, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-4 1/4 Cor. bet. Sec's. 7-8, set by Geo. H. Cannon D.S. in 1854. Bearings were:
Y. Pine 16", N60°W, 50 lks. and Sp. Pine 5", S65°E, 8½ lks.

3-Sec. 8 North 1/16 corner bet. Sections 7-8.
1-Sec. 8 West 1/16 corner bet. Sections 5-8.
4-Sec. 8 Northwest 1/16 corner of Section 8.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-4 Re-established corner by single proportionate measure and on a line deflecting 0° 05' as recorded.

3-Sec. 8 Placed corner midway bet. sec. cor. to North and 1/4 corner to South.
1-Sec. 8 Placed corner midway bet. sec. cor. to West and 1/4 corner to East.
4-Sec. 8 Placed corner at intersection of lines quartering the quarter section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum, cap at all corners. Bearings:

C-4 6" J. Pine, N27°W, 7.6' & 7" J. Pine, S73°E, 37.7' & 8" R. Pine, S12°W, 43.4'.
3-Sec. 8 6" J. Pine, S30°W, 8.5' & 6" J. Pine, N54°W, 14.8' & 8" J. Pine, N81°E, 17.3'.
1-Sec. 8 12" R. Pine, N77°E, 71.2' & 14" Twin R. Pine, S47°W, 83.2' and Corner buried in center of E-W Road.
4-Sec. 8 12" R. Pine, S26°E, 14.7' & 10" R. Pine, N76°W, 39.2' & 6" J. Pine, N27°E, 7.0'.

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE

7-22-81

SURVEYOR'S MICHIGAN REGISTRATION NO.

8887

