

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

4 Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 10 X. W.	D-3, F-3
2. PROPERTY CONTROLLING IN SECTION	4, T. 49 N. R. 10 X. W.	8, 9
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1976 & 1978, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-3 South 1/4 Corner of Section 5. DNR on 6-6-58. 7" J. Pine, S31°E, 35 lks. & 9" J. Pine, N16°E, 15 lks.
- F-3 South 1/4 Corner of Section 4. DNR on 6-6-58. 10" J. Pine, N1°W, 42 lks. & 13" R. Pine, S54°E, 31 lks.
- 8 West 1/16 Corner of Section 4. DNR on 1-13-77. 8" J. Pine, S14°W, 13.0' & 12" J. Pine, S82°E, 11.6'.
- 9 East 1/16 Corner of Section 4. DNR on 1-13-77. 24" R. Pine, S80°W, 32.7' & 20" R. Pine, S7°W, 18.0'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-3 Both witt. have been cut. Re-witt this corner set by myself on 6-6-58, from an O.B.T.
- F-3 N.W. J. Pine bearing tree has been cut. Re-witt. this corner as placed by myself 6-6-58, from O.B.T'S.
- 8 Witt. have been cut. Re-witt. this corner as placed by myself on 1-13-77, midway bet. 1/4 corner and center corner.
- 9 Both witt. have been cut. Re-witt. this corner as placed by myself on 1-13-77, midway bet. center corner and east 1/4 corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-3 Re-witt. monument. Bearings: 6" J. Pine, N16°E, 31.87' & 8" J. Pine, N68°E, 27.80' & O.B.T. W. Pine Stump, S50°E, 42.9'.
- F-3 Re-witt. monument. Bearings: 16" R. Pine, N46°W, 55.6' & 13" R. Pine, S54°E, 20.46'.
- 8 Re-witt. monument. Bearings: 6" Twin R. Pine, S24°E, 72.25' & 6" Oak, S84°E, 73.65' & 6" R. Pine, N50°E, 49.7'.
- 9 Re-witt. monument. Bearings: 20" R. Pine, N84°W, 50.8' & 6" J. Pine, N46°E, 42.4' & 6" R. Pine, N30°W, 5.6'.

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE 9-25-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

