

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Luce Co.

4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 49 <sup>N.</sup> <del>X</del> , R. 10 <sup>W.</sup> <del>X</del>	L-3, C-9, C-10, G-2A
2. PROPERTY CONTROLLING IN SECTION.....	T. ...., S., R. ...., E., W. ....	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. ...., S., R. ...., E., W. ....	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1976 & 1977, 19....., established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on....., 19...., found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-3 South 1/4 Cor. of Sec. 1. DNR in 1957. 10" J. Pine, S25<sup>0</sup>E, 60 lks. & 7" J. Pine, N24<sup>0</sup>E, 49 lks.
- C-9 S.E. Sec. Cor. of Sec. 19. DNR on 12-27-57. 7" J. Pine, N32<sup>0</sup>E, 41 lks. & 8" J. Pine, S31<sup>0</sup>W, 52½ lks. & 10" J. Pine, N48<sup>0</sup>W, 30 lks.
- C-10 East 1/4 Cor. of Sec. 30. DNR on 6-2-58. 9" J. Pine, S41<sup>0</sup>E, 55½ lks. & 9" J. Pine, N70<sup>0</sup>W, 103 lks.
- G-2A M.C. bet. Sec's. 3-4 on Lake Superior. 16" W. Birch, S5<sup>0</sup>E, 130 lks. & 8" R. Pine, N65<sup>0</sup>E, 126½ lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-3 Both NBT'S had been cut. Re-witt this corner as set by myself in 1957, from a corner perpetuated by R.L.S. Schaff.
- C-9 S.W. and N.W. N.B.T'S. had been cut. Re-witt this corner as placed by myself 12-27-57, from an O.B.T.
- C-10 Re-witt. this corner as placed by myself 6-2-58, from two O.B.T'S.
- G-2A W. Birch N.B.T. is dead. Re-witt. this corner as placed by myself in 1957.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-3 Re-witt monument. Bearings: 10" J. Pine, S79<sup>0</sup>W, 55.8' & 5" Maple, S24<sup>0</sup>W, 43.8'.
- C-9 Re-witt monument. Bearings: 6" Oak, S19<sup>0</sup>E, 40.5' & 8" Oak, N40<sup>0</sup>W, 47.1' & 2" Iron Pipe, N32<sup>0</sup>E, 2.6' & 7" J. Pine Stump, N32<sup>0</sup>E, 27.06'.
- C-10 Re-witt monument. Bearings: 14" W. Pine, N37<sup>0</sup>W, 131.8' & 6" J. Pine, N61<sup>0</sup>E, 39.4' & 9" J. Pine, S41<sup>0</sup>E, 36.63' & 9" J. Pine Stump, N70<sup>0</sup>W, 67.98'.
- G-2A Re-witt monument. Bearings: 14" R. Pine, N38<sup>0</sup>W, 43.0' & 8" R. Pine, N65<sup>0</sup>E, 83.49'.

SIGNED BY:

*Billy D. Buckler*  
Billy D. Buckler

DATE 9-25-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

