

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

4 Corners.

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 49 N. R. 10 W.	B-3, A-3, B-9, E-4
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. ...., RECORDED PLAT.....		
5. PRIVATE CLAIMS.....		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1976 & 1977, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-3 South 1/4 Corner of Section 7. DNR on 5-6-1952. 1" pipe with brass cap. Witt: 14" Red Pine, N44<sup>0</sup>W, 38 lks.
- A-3 S.W. Section Corner of Section 6. DNR on 5-13-52. 1" pipe with brass cap. Witt: 9" Red Pine, S20<sup>0</sup>E, 24 lks. & 10" Red Pine, N6<sup>0</sup>W, 76 lks.
- B-9 South 1/4 Corner of Section 19. DNR on 5-6-52. 1" pipe with brass cap. Witt: 9" J. Pine, N60<sup>0</sup>W, 71 lks. & 9" Scotch Pine, S50<sup>0</sup>E, 53 lks.
- E-4 East 1/4 Corner of Section 8. DNR on 5-6-52. 1" pipe with concrete base. Witt: 12" Red Pine, N67<sup>0</sup>E, 17 lks. & 10" Red Pine, N82<sup>0</sup>W, 53 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-3 Added a new bearing tree to this corner as set by myself in 1952 from an OBT.
- A-3 N.W Red Pine bearing tree had been cut. Re-witt. this corner as set by myself in 1952.
- B-9 N.W. J. Pine bearing tree had been cut. Re-witt. this corner as set by myself in 1952, from 2 obt's.
- E-4 Re-placed monument set by myself in 1952 that had been taken out.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-3 Re-witt monument. Bearings: 14" R. Pine, N44<sup>0</sup>W, 25.08' & 10" J. Pine, South, 27.2'.
- A-3 Re-witt monument. Bearings: 9" R. Pine, S20<sup>0</sup>E, 15.84' & 6" W. Pine, S64<sup>0</sup>W, 17.9'.
- B-9 Re-witt monument. Bearings: 9" Scotch Pine, S50<sup>0</sup>E, 34.99' & 16" R. Pine, N13<sup>0</sup>E, 61.3'.
- E-4 Re-placed monument w/1" pipe with DNR Cap. Bearings: 12" R. Pine, N67<sup>0</sup>E, 11.22' & 10" R. Pine, N82<sup>0</sup>W, 34.98'.

SIGNED BY

*Billy D. Buckler*  
Billy D. Buckler

DATE 9-25-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

