

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LUCE (County)	Located In:	Corner Code //
1 Public Land Survey	T 49N R 10W	I-10
	T 49N R 10W	M-6
	T 49N R 10W	G-4
	T R	
2 Property Controlling in Section	S T R	
3 Miscellaneous Property in Sec	S T R	
4 Lot No	Recorded Plat	
5 Private Claims		

Register of Deeds Stamp & File Number

I, **Gerald L. Wiggins** in a field survey on 5-29- 19 91
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law, established, re-established, monumented, re-monumented, recovered, found as
expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A Description of original monument and accessories and/or subsequent restoration:

- I-10 Section Corner 22,23, 27,26. Set by Billy D. Buckler R.L.S. on May 22, 1952. DNR Monument.
8" J. Pine, S80W, 76 lks. & 9" R. Pine, N4°E, 76 lks.
- M-6 East 1/4 Corner of Section 13. Set by Billy D. Buckler, R.L.S. on March 13, 1958.
DNR Monument. 7" J. Pine, N52°E, 23 lks. & 7" J. Pine, N50°W, 37 lks.
- G-4 1/4 Corner between sections 9 and 10. Set by Billy D. Buckler, R.L.S. 8-18-1972.
DNR Monument. 10" W. Pine, N87°E, 14.0' & 10" R. Pine, S4°E, 41.8'

B Description of corner evidence found and/or method applied in restoring or reestablishing corner.

- I-10 Both witness trees have been cut, marked new trees.
- M-6 Both witness trees have been cut, marked new trees.
- G-4 Both witness trees have been cut, marked new trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner
DNR Monument at all three corners.

- | | | |
|--------------------------------|-------------------------------|-------------------------------|
| I-10 14" R. Pine, N68°W, 33.5' | M-6 12" J. Pine, N65°E, 22.0' | G-4 6" W. Birch, North, 27.4' |
| 8" W. Pine, S63°W, 23.9' | 8" R. Pine, S83°E, 39.9' | 4" Balsam, N14°W, 23.3' |
| 8" R. Pine, S42°W, 28.1' | 6" R. Pine, S67°E, 35.3' | 6" Maple, N60°W, 39.4' |
| 8" R. Pine, S31°W, 32.6' | 14" J. Pine, S45°E, 25.0' | 5" Balsam, N70°W, 49.5' |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4				3		2				
3													
4	7	8	9				10		11				
5													
6	18	17	16				15		14				13
7													
8	19	20	21				22		23				24
9													
10	30	29	28				27		26				25
11													
12	31	32	33				34		35				36
13													

Signed by *Gerald L. Wiggins*
Gerald L. Wiggins
Surveyor's Michigan License No 23521

Date 6-26-91

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1982

