

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LUCE

(County)

Located In:

Corner Code #/

- | | | | | | |
|------------------------------------|---|---------------|---|-----|-----|
| 1. Public Land Survey | T | 49N | R | 10W | L-5 |
| | T | 49N | R | 10W | M-5 |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec | S | T | R | | |
| | S | T | R | | |
| 4. Lot No | | Recorded Plat | | | |
| 5. Private Claims | | | | | |

Register of Deeds Stamp & File Number

I, **Gerald L. Wiggins** in a field survey on 5-29, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

- L-5 1/4 Corner between 12 and 13. Corner was set by Billy D. Buckler R.L.S. on March 13, 1958. DNR Monument and 6" J. Pine, N22°E, 17 lks. & 7" J. Pine, S34°E, 19 lks.
- M-5 Section Corner 12 and 13 on township line. Corner set by Billy D. Buckler, R.L.S. on March 13, 1958. DNR Monument and 7" J. Pine, N68°W, 66 lks. & 9" J. Pine, S52°W, 46 1/2 lks.

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-5 Replaced Buckler's monument which had been bent out and marked new witnesses.
- M-5 Buckler's monument still in place S.W. J. Pine is still alive N.W. J. Pine is dead, marked new witnesses.

C Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 Buried a 1" pipe W/plastic R.L.S. Cap. M-5 DNR Monument.

12" J. Pine, S67°W, 26.5'
 10" J. Pine, N34°W, 12.6'
 6" J. Pine, N22°E, 11.22'
 7" J. Pine, S34°E, 12.54'

10" J. Pine, S15°E, 64.55'
 6" J. Pine, S45°E, 41.3'
 8" J. Pine, N89°E, 41.65'
 12" J. Pine, S52°W, 30.7'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by

Gerald L. Wiggins
 Gerald L. Wiggins

Surveyor's Michigan License No.

23521

Date 6-26-91

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN 24, 1982
 REVISION MAY 1982

