

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce
(County)

Located in: Corner Code #

1. Public Land Survey T R
T R
T R
T R

2. Property Controlling in Section S 10 T 43 R 10W
S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jun 17 1936

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1	6	5	4	3	2	1						
2												
3	7	8	9	10	11	12						
4												
5	18	17	16	15	14	13						
6												
7	19	20	21	22	23	24						
8												
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
(1-Sec. 10) West 1/16 corner between Sections 3-10. Corner established in 1971 by Billy D. Buckler, RLS, midway and on line between Sec. Cor. to west and 1/4 Cor. to East. Corner monument: 1" pipe with 4" aluminum cap. Witnesses to corner: 20' R. Pine S05E 50.7', 8' R. Pine N63E 41.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 10) Found the 1971 monument, as described, in good condition, at record bearing and distance from the two 1971 witness trees. Both recovered in good condition. Determined the corner monument to be 0.79' East and 0.49' North of the position intended in 1971 and accepted it as a careful and faithful determination of the position of the corner. Left the monument in place, made new BH markings on the 1971 witnesses, and marked two new accessories as described below. Corner recovered and re-witnessed by T. Stark and D. Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1-Sec. 10) Found 1" iron pipe with 4" MONA cap. Blazed, scribed, and set measuring nails in the following:
23' R. Pine S07E 51.7' "W1/16"
12' R. Pine N68E 42.05' "W1/16"
8' R. Pine S20W 15.3' "W1/16 BT"
9' R. Pine N22W 16.25' "W1/16 BT"
Placed a 5" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date Jan. 22, 1997

For the Michigan Department of Natural Resources - Forest Management Division