

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 19W	H4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 10 T 49N R 19W	7
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 10 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(H4) Center of Section 10. Corner not established in the original survey. found no subsequent record.
 (7-Sec. 10) North 1/16 corner between Section 10-11. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H4) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/4 corners 2638.36' North, 2641.54' East, 2645.35' South, and 2645.30' West. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum WDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.
 (7-Sec. 10) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Section corner 1315.45' North and 1/4 corner 1315.45' south. At the position for the corner, I buried a 1" I.D. x36" iron pipe capped with a 4" dia. cast aluminum WDNR tablet, appropriately stamped. This monument falls in a cleared firelane. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H4) Set 1" dia. iron pipe with 4" WDNR cap. Blazed, scribed, and set measuring nails in the following: 6" Maple S40E 9.3' 8" J. Pine S02W 27.5' 10" J. Pine S32E 21.05' 18" W. Pine N02E 38.0' Placed a squared and scribed cedar post adjacent. Bearings are magnetic.	(7) Set 1" iron pipe with 4" WDNR cap. Blazed, scribed, and set measuring nails in the following: 14" R. Pine N63E 22.35' "N1/16 BT" 10" R. Pine S44E 16.85' "N1/16 BT" 12" R. Pine S16E 36.5' "N1/16 BT" 4" J. Pine N52W 12.25' "N1/16 BT" Placed a location poster on a Cedar post 5' east of the monument. Bearings are magnetic.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 1-22-97

For the Michigan Department of Natural Resources - Forest Management Division