

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce

(County)

Located in:

Corner Code #

1. Public Land Survey

T 49N R 10W 13

T 49N R 10W 65

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Jun 17 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5							●						
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(13) Corner common to Sections 2-3-10-11. Corner re-monumented in 1957 at the original position as determined by recovered original bearing trees by Billy D. Buckler, ALS. Buckler placed a 1" x 4 ft. iron pipe buried 6" deep at the corner and marked the following: 6" Jackpine N63W 103 links, 8" Jackpine S74W 174 links. Found no subsequent record.

(65) Corner common to Sections 9-10-15-16. Corner re-monumented in 1958 by Billy D. Buckler, ALS. Replaced corner in intersection of firelanes. Found evidence of old post in soil. found Yellow Pine B.T. to NW, down, could not determine exact position of B.T. Found stump hole S61W 26 links. Corner monument: 2" iron pipe buried in intersection of N-S-E-W firelanes. Witnesses to corner: 15" Red Pine N31E 73 links, 12" White Pine S86E 102 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13) Recovered the 1957 monument, as described, in good condition, at record bearing and distance from the 1957 Jack Pine witnesses, both standing. The Jack Pine N63W is now dead. That S74W is green. Re-marked the top blaze of this tree, placed a measuring nail with tag in it, and marked three new bearing trees as described below. Corner recovered and re-witnessed by T.Stark and D.Lampela, Newberry District Office.

(65) Recovered a 1" iron pipe capped with a 4" brass Michigan Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1958 witnesses, both in good condition. Accepted the monument as marking the position determined in 1958 by Buckler. Left the monument in place, made new BH markings on the 1958 witness trees, and made two new witnesses as described below. Corner recovered and re-witnessed by T.Stark and D.Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) Found 1" iron pipe 6" below ground surface. Blazed, scribed, and placed measuring nails in the following:

10" J. Pine S73W 115.95' "S10"
 8" J. Pine N63E 37.85' "S2 NBT"
 6" J. Pine S25E 38.8' "S11 NBT"
 5" J. Pine N59W 25.95' "S3 NBT"
 Bearings are magnetic.

(65) Found brass capped MI Dept. of Conservation monument, buried. Blazed, scribed, and set measuring nails in the following:

17" Red Pine N34E 48.65' "S10"
 13" White Pine S60E 67.65' "S15"
 12" J. Pine S35E 15.65' "S15 NBT"
 12" R. Pine N28W 23.25' "S3 NBT"
 Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

1-22-97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division