

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce

(County)

Located in:

Corner Code #

1. Public Land Survey

T	R	_____
T	R	_____
T	R	_____
T	R	_____

2. Property Controlling in Section

S	10	T	49N	R	10W	10
S	10	T	49N	R	10W	2

3. Miscellaneous Property in Sec.

S	T	R	_____
S	T	R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

2 Jun 17 1996

10 Sep 10 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 10) South 1/16 corner between Sections 9-10. Corner not established in the original survey. Found no subsequent record.
 (2-Sec. 10) East 1/16 corner between Sections 3-10. Corner established in 1971 by Billy D. Buckler, RLS. Corner placed midway and on line bet. Sec. Cor. to east and 1/4 Cor. to west. Corner lies on North side of E-W firelane. Corner monument: 1" pipe with 4" aluminum cap. Witnesses to corner: 8" R. Pine N14W 12.9', 10" J. Pine S30W 56.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 10) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between 1/4 Corner 1324.12' North and Section corner 1324.12' South. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.

(2-Sec. 10) Recovered The 1971 monument, as described, in good condition, and at record bearing and distance from the Red Pine witness, found in good condition. The J. Pine witness from 1971 was not recovered. Left the monument in place, made new marks at B- on the 1971 R. Pine, and marked three new witnesses as described below. Corner recovered and witnessed by T.Stark and D.Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1" iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 12" R. Pine S65E 6.55' "S1/16 BT" 3" Maple N51E 17.1' "S1/16 BT" 4" Maple N27E 24.15' "S1/16 BT" 16" R. Pine N15W 82.85' "S1/16 BT" Placed a 5" squared and scribed Cedar post adjacent. Bearings are magnetic.	(2) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 12" R. Pine N16W 13.25' "E1/16" 4" J. Pine S34W 17.8' "E1/16 BT" 5" R. Pine N84W 13.55' "E1/16 BT" 12" R. Pine N25E 26.0' "E1/16 BT" Placed a 8" squared and scribed cedar post adjacent. Bearings are magnetic.
--	---



Signed by

Stephan J. Szyszkoski

Date

1-22-97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division