

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>7</u> T <u>49N</u> R <u>10W</u>	<u>7</u>
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		11		12		13		14		15	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 03/31/2011 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 7) North 1/16 corner between Sections 7 and 8. 1981 - Established by Billy D. Buckler RLS midway and on line between Section and Quarter corners. Set 1" ID I.pipe with 4" aluminum cap. 6" J.Pine S30W 8.5', 6" J.Pine N54W 14.8', 8" J.Pine N81E 17.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 7) Found the 1981 monument in good condition and substantially at the record position between adjacent corners. The 1981 witness trees were not recovered. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 8" J.Pine S52E 14.2' mrkd "N1/16 BT"
 9" J.Pine S13E 20.45' do
 9" W.Birch S85W 28.3' do
 17" R.Pine N17W 77.0' do
 Bearings are magnetic.



Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 05/04/2011

For the Michigan Department of Natural Resources, Office of Land and Facilities