

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey | T <u>49N</u> R <u>10W</u> | <u>I4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Nov 02 1995

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(I4) Quarter corner common to Sections 10-11. Corner remonumented and recorded by Billy D. Buckler in 1958: "Replaced corner as set by Marcus Schaaf, Reg. Surveyor. Found 2" iron pipe in place with Yellow Birch stump bottoms, N73W 17 links and S59E 14 links. Placed 1" pipe with 4" Brass Cap, 12" Hemlock S81E 37 links, 10" Yellow Birch N08W 39 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I4) Found and accepted Buckler's monument as described, in good condition, and at record bearing and distance from the 1958 witnesses, both in good condition. Left the monument in place, marked new top blazes on the 1958 trees, and placed measuring nails in them. Marked two new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I4) Found 1" pipe with 4" brass Mich. Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
 12" Hemlock S81E 24.95' "1/4S"
 10" Y. Birch N08W 26.05' "1/4S"
 24" H. Maple S02W 11.7' "1/4S NBT"
 12" Hemlock N77W 20.05' "1/4S NBT"
 Placed a new cedar post adjacent.
 Bearings are magnetic (1958 bearings are record).



Signed by Stephan J. Szyszkoski Date 4/12/00
 Surveyor's Michigan License No. 33986