

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce

(County)

Located In:

Corner Code #

1. Public Land Survey

T 49N R 10W      82  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S 6 T 49N R 10W      13  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jun 06 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	●		5		4		3		2		1	
3	●											
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**


(82) Center of Section 6. Established in 1965 by F.J.Bray at the intersection of N-S and E-W 1/4 lines. 1" iron pipe with 4" aluminum cap. 10" Jack Pine S44E 49.5 links, 9" Jack Pine S55W 34 links.  
 (13-Sec. 6) Southeast 1/16 corner, Section 6. Established in 1965 by F.J.Bray RLS at the calculated intersection of the East and South 1/16 lines. 1" iron pipe with 4" aluminum cap. 7" Jack Pine S30E 11 links, 7" Jack Pine N39W 23 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(82) Recovered the 1965 monument as described, in good condition, and at record bearing and distance from the 1965 witness trees. The J.Pine SE is dead and down on the ground. The J.Pine SW is in good condition. Left the monument in place and made new accessories as described below.  
 (13-Sec. 6) Recovered the 1965 monument as described, in good condition, and at record bearing and distance from the 1965 witness trees. The J.Pine SE is now a 3' stump with scribing visible. The J.Pine NW is in good condition with scribing visible. Left the monument in place and made new accessories as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(82) Found 1" ID iron pipe with 4" alum. State of Michigan tablet. Blazed, scribed, and set measuring nails in:	(13-Sec. 6) Found 1" ID iron pipe with 4" alum. State of Michigan cap. Blazed, scribed, and set meas. nails in:
12" J.Pine S57W 23.1' "CS"	10" J.Pine N38W 15.45' the 1965 wit.
5" W.Pine S25W 22.3' "CS 8T"	5" R.Pine S16W 4.15' "SE1/16 8T"
14" R.Pine North 39.0' do	6" J.Pine S60E 8.1' do
12" R.Pine N28E 42.8' do	5" W.Birch N77E 24.2' do
C/L E-W trail North 13.5'	Cedar post adjacent. Bearings are
Cedar post adjacent. Bearings are magnetic. Distances to nail with tag.	magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/3/01

For the Michigan Department of Natural Resources - Office of Property Management