

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce

 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|------------|---------------------------|----------------------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S <u>6</u> | T <u>49N</u> R <u>10W</u> | <u>1/64 9-C2</u> |
| | S <u>6</u> | T <u>49N</u> R <u>10W</u> | <u>SMC GVT LOT 1</u> |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 06 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(9-C2) C-E-E 1/64 corner, Section 6. Corner not established in the original survey.

(SMC GVT LOT 1) Special Meander Corner on the E-E 1/64 line, Section 6, being on the East line of the West 1/2 of Gov't Lot 1 at it's intersection with the bluff overlooking Lake Superior. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-C2) Established the corner midway and on a straight line between 1/16 corner 657.80' west and Quarter corner C2 657.80' east. From the corner thus established, the centerline of an E-W trail is north, 20 feet distant.

(SMC GVT LOT 1) Established the corner on the E-E 1/64 line, Section 6, which is a line passing through the C-E-E 1/64 corner and having a bearing which is the mean of the East 1/16 line and the East line of Section 6. The position thus established is 952.94 feet north of the C-E-E 1/64 corner which position is not necessarily the intersection with the original GLO meander of Lake Superior. The corner was placed on the 1/64 line at a convenient location on the bluff.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9-C2) Set 1 10x36 iron pipe with 4 alum. MDNR cap. Blazed, scribed, and set measuring nails with tag in:
 6" J.Pine N30W 5.6' "1/64 BT"
 6" R.Pine S19W 8.5' do
 12" W.Birch N07E 33.4' do
 8" R.Pine S75E 28.05' do

Placed wood post adjacent. Bearings are magnetic. Distances to nail with tag.

(SMC) Set 1 10x36 iron pipe with 4 alum. MDNR tablet. Blazed, scribed, and set measuring nails with tags in:
 10" W.Pine S40E 30.75' "BT"
 8" W.Pine South 3.7' "BT"
 4" W.Pine S65W 13.95' "BT"
 4" W.Pine N72W 7.85' "BT"

Set wood post adjacent. Bearings are magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/3/01

For the Michigan Department of Natural Resources - Office of Property Management