

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>3</u> T <u>49N</u> R <u>10W</u>	<u>8</u>
	S <u>3</u> T <u>49N</u> R <u>10W</u>	<u>SMC NORTH OF COR. #B</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Dec 01 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 3) West 1/16 corner Section 3. Not established in the original survey.  
 (MC north of 8) Special meander corner on the West N-S 1/16 line north of the West 1/16 corner of Section 3. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 3) Established the corner midway and on a straight line between Quarter corner 1323.14' West and Center of Section (unmonumented) 1323.14' East.  
 (MC north of 8) Established the corner on the 1/16 line, the direction of which is the mean of the bearings of the West line of the Section and the N-S 1/4 line of Section 8, and 339.27' north of the West 1/16 corner of Section 8. This position is not intended to denote the high water mark but is only a position of convenience. The water's edge of Lake Superior is approximately 350' north of this position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 14" J.Pine S77W 6.15' mrkd "W1/16 8T" 10" W.Pine N82E 10.95' do 6" Maple N58E 24.15' do 4" W.Pine North 18.7' do	(MC) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" J.Pine S50E 53.95' mrkd "MC NBT" 8" W.Birch S22E 46.5' do 14" W.Pine S07W 52.9' do 12" R.Pine S50W 68.9' do
Bearings are magnetic. Distances are to nail with tag. Placed cedar post adjacent.	Bearings are magnetic. Distances are to nail with tag.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/20/04

For the Michigan Department of Natural Resources, Office of Land and Facilities