

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T ___ R ___		
	T ___ R ___		
	T ___ R ___		
	S ___ T ___ R ___		
2. Property Controlling in Section	S <u>2</u> T <u>49N</u> R <u>10W</u>		<u>10</u>
	S <u>2</u> T <u>49N</u> R <u>10W</u>		<u>9</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___		
	S ___ T ___ R ___		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims

	9	Nov	08	2004
	10	Nov	04	2004

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 2) South 1/16 corner between Sections 2-3. Not established in the original survey.
 (9-Sec. 2) East 1/16 corner, Sec. 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 2) Established the corner midway and on a straight line between Section corner 1317.25' south and Quarter corner 1317.25' north. From the corner thus established, a fence line is East approx. 10 feet distant.
 (9-Sec. 2) Established the corner at the intersection of the E-W 1/4 line of Sec. 2 with the East N-S 1/16 line as monumented in 1995 by Eino Sainio, PS 7873, and subsequently by Keith Waters, PS 33142.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" J.Pine N39E 3.35' mrkd "S1/16 BT" 10" J.Pine S40W 8.95' do 6" J.Pine S24W 34.35' do 6" J.Pine S76E 32.85' do Bearings are magnetic. Distances are to nail with tag.	(9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" J.Pine N60E 12.15' mrkd "E1/16 BT" 6" J.Pine N16W 13.9' do 10" J.Pine S69W 13.3' do 5" W.Pine S28W 32.85' do Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/20/04

For the Michigan Department of Natural Resources, Office of Land and Facilities