LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce (County)

		Located In:	Corner Code #
1. Public Land Survey		T 49N R 10W	J2
		T R	
		T R	
	S	T R	
2. Property Controlling	S 2	T 49N R 10W	12
in Section	S	T R	
3. Miscellaneous	S	T R	
Property in Sec.	S	T R	

Register of Deeds Stamp & File Number

4. Lot No. _____ , Recorded Plat_____

5. Private Claims



Nov 08 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J2) Center of Section 2. Not established in the original survey.
(12-Sec. 2) South 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J2) Established the corner at the intersection of the E-W 1/4 line (straight line between 1/4 corners), and the N-S 1/4 line (mean bearing of east and west lines of the section).
(12-Sec. 2) Established the corner midway and on a straight line between Center of Section 1315.71' north and Quarter corner 1315.71' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
20" W.Pine S88E 9.4' mrkd "CS BT"
18" R.Pine S11E 29.75' do
5" W.Pine N08E 9.65' do
12" J.Pine S87W 73.0' do
Bearings are magnetic. Distances are to nail with tag.

(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
3" J.Pine S06E 10.8' mrkd "S1/16 BT"
5" J.Pine N28W 6.45' do
4" J.Pine S74W 13.25' do
5" J.Pine S50E 23.95' do
Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.

STATE OF MICHIGAN
STEPHAN J. SZYSZKOSKI
LAND SURVEYOR
No. 33986
LICENSED LAND SURVEYOR

Signed by Stephan J. Szyszkoski Date 12/20/04

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
Revised May 14, 1975
Revised Jan., 1983
Rervised Oct., 1995