

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
	T <u>    </u> R <u>    </u>		
	S <u>    </u> T <u>    </u> R <u>    </u>		
2. Property Controlling in Section	S <u>2</u> T <u>49N</u> R <u>10W</u>		14
	S <u>2</u> T <u>49N</u> R <u>10W</u>		13
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>		
	S <u>    </u> T <u>    </u> R <u>    </u>		

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Nov 09 2004

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(14-Sec. 2) South 1/16 corner between Sections 1-2. Not established in the original survey. Established and monumented with a T-iron in 1995 by Eino Sainio, PS 7873.  
 (13-Sec. 2) Southeast 1/16 corner, Sec. 2. Not established in the original survey. Established and monumented in 1995 with a capped T-iron by Eino Sainio, PS 7873. Keith Waters, PS 33142 subsequently used this position to control a subdivision of Mr. Sainio's 1995 survey in the NE 1/4 of the SE 1/4 and in Gov't Lot #1 of Sec. 2

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(14-Sec. 2) Found and accepted the T-iron placed by Mr. Sainio in 1995, it being substantially midway between the Section corner to the south and the Quarter corner to the north.  
 (13-Sec. 2) Recovered and accepted the 1995 monument.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(14) Found T-iron with metal post adjacent. Set measuring nails in: 20" R.Pine N33E 31.35' mrkd "S1/16 8T" 4" J.Pine S30E 5.95' do 7" J.Pine S80W 9.3' do 6" J.Pine N54W 11.0' do Bearings are magnetic. Distances are to nail with tag.	(13) Found capped T-iron with metal post adjacent. Set measuring nails in: 7" J.Pine S36W 5.6' mrkd "SE1/16 8T" 6" J.Pine S70W 16.4' do 6" J.Pine N47W 3.7' do 7" J.Pine N51E 35.8' do Bearings are magnetic. Distances are to nail with tag.
---	--

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 12/20/04

For the Michigan Department of Natural Resources, Office of Land and Facilities