

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T 49N R 10W	MC north of I2	
	T 49N R 10W	I2	
	T R		
	S T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 04 2004

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1									LAKE				
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(MC north of I2) Meander corner on the shore of Lake Superior between Sections 2 and 3. 1957 - Billy D. Buckler, RLS established a witness corner 2.50 chains south of the record GLO position on the extension of the line between I3-I2, 7.50 chains north of I2. Set 1" pipe with 4" brass cap. 8" twin Red Pine S32W 61 links, 10" Red Pine S13E 103 links.
 (I2) Quarter corner common to Sections 2-3. 1957 - Recovered and recorded by Billy D. Buckler RLS: "Replaced 1/4 corner from one jackpine BT bearing N45E 30 links. BT in good condition. Found 2" pipe in concrete set by Marcus Schaff, Reg. Surveyor. 1/4 Corner lies in N-S fire line. Set 1" pipe with 4" brass cap. 20" Red Pine N71W 69 links, 6' Red Pine N59E 44 links."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC north of I2) The 1957 monument was not recovered. Remonumented the 1957 position for the corner from the two 1957 BTs, both found in good condition with overgrown blazes. The position is 10.1' west of a straight line produced through I3 and I2 as now monumented, and is 494.4' north of I2. The position for the corner falls on a bluff-tree line about 200' south of the present lake edge.
 (I2) The 1957 1" pipe with brass cap was not recovered. Found a 2" pipe in a concrete base at record bearing and distance from the 1957 witness trees, both recovered in good condition, with markings visible. Accepted the pipe as the best available evidence of the position of the original corner and made new witnesses. The fire lane is now 10' east of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Set 1" IDx36" I. pipe with 4" alum. MDNR cap. Set measuring nails in:	(I2) Found 2" ID I. pipe in a concrete base. Set measuring nails in:
12" twin R. Pine S36W 40.3' mrkd "WC" *	26" R. Pine N66W 46.0' old blazes *
14" R. Pine S09E 68.85' do *	12" R. Pine N58E 29.4' mrkd "1/4S" *
6" J. Pine S55E 44.6' mrkd "WC BT"	6" R. Pine S61W 15.2' mrkd "1/4S NBT"
6" R. Pine S80W 19.3' do	12" W. Pine S25E 6.95' do
Bearings are magnetic. Distances are to nail with tag. * denotes 1957 BT	Bearings are magnetic. Distances are to nail with tag. * denotes 1957 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/20/04

For the Michigan Department of Natural Resources, Office of Land and Facilities