

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T 49N R 10W	A11	
	T 49N R 11W	M11 (same corner)	
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

T49N R10W

I, Stephan J. Szyszkoski, in a field survey on 07/07/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to Sections 30-31 T49N-R10W and Sections 25-36 T49N-R11W. 1841 - Established by John Burt, Deputy Surveyor: Set post. Spruce 6" N65W 24 links, Hemlock 7" N61E 12 links. Circa 1920 - Remonumented by Marcus Schaaf RLS. Schaaf's record has not been found. 1957 - Remonumented by Billy D. Buckler RLS: "Replaced section corner as set by Marcus Schaff, Reg. Surveyor. Found 2" pipe in concrete. No evidence of original witnesses. Section corner lies in line with fire lane to east and 20 links south of fire lane from west". Set 1" pipe with 4" brass cap. 12" Jackpine S3W 7 links, 11" Jackpine N8W 77.5 links, 11" Red Pine S84E 125.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 1957 monument and adjacent 2" iron pipe in concrete badly bent. I accept the 1957 position as the best available evidence of the position of the original corner and replace the bent 1957 pipe with a new monument. Two remaining 1957 NBTs are found at record bearing and distance: The Jackpine NW is in good condition, the Red Pine SE is standing dead. The Jackpine SW is windthrown.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 15" J.Pine N06W 51.5' mrkd "S25" 1957 NBT
 8" R.Pine N68E 78.55' mrkd "S30 NBT"
 12" R.Pine S23W 50.2' "S36 NBT"
 14" R.Pine N62W 65.15' "S25 NBT"
 Bearings are magnetic.



Signed by *Stephan J. Szyszkoski* Date 01/26/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities