

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 10W	B11
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/07/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 30 and 31. 1854 - Established by George Cannon Deputy Surveyor, 40.00 chains west of Section corner C11 and 36.54 chains east of Section corner A11, and on line between them. Set post. Beech 9" N10W 17 links, W.Pine 20" S50E 48 links. 1952 - Remonumented by Dean C. DeLaMater RLS at the original position: "This corner was pointed out to me by B. McTiver, District Forester, of Newberry. One original B.T. still in place, fair condition. Corner was placed and witnessed May 7, 1952." Set 1" pipe with 4" brass cap. New witnesses: 6" W.Pine N37W 31 links, 8" R.Pine S22W 42 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original post and accessories were not recovered. The monument described in the 1952 record was not recovered. Found a 2" iron pipe set in a concrete base (such as had been set by Marcus Schaaf RLS in this area) leaning against a nearby tree, completely out of the ground. Recovered the 1952 witnesses, both in good condition and reestablished the corner position at record bearing and distance from those witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 14" R.Pine S25W 27.85' mrkd "1/4S" 1952 NBT
 13" W.Pine N32W 20.3' do do do
 14" R.Pine N63E 30.2' mrkd "1/4S NBT"
 8" R.Pine S47E 23.5' do do do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/25/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities