

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 49N R 10W	E5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/09/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E5) Corner common to Sections 8-9-16-17. 1854 - Record of Geo. H. Cannon, Deputy Surveyor states: Set post and restored old bearings. Spruce 8" S15W 23 links, Y.Pine 10" S69E 45 links. 1958 - Record of Billy D. Buckler, RLS: "Replaced corner from stump hole bearing S69E 45 links and in intersection of E & W Firelane and County Road. Corner was placed by Marcus Schaaf, Reg. Surveyor but has since been removed according to testimony of B. McTiver, District Forester". Set 3/8"x32" iron bar. 16" Red Pine N37E 45 links, 16" Red Pine S47W 51 links. Found no other record of the Schaaf survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E5) Found the 3/8" iron bar monument of record, in good condition, and at record bearing and distance from the 1958 NBTs, both in good condition with overgrown blazes. Accepted same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E5) Fd. 3/8" iron bar at intersection of FireLane with Co. Rd. #410 Set measuring nail with MDNR tag in the side of:
 18" R. Pine N42E 30.5' mrkd "S9" 1958 NBT
 18" R. Pine S50W 34.32' "S17" do
 12" R.Pine N66W 40.5' mrkd "S8 NBT"
 11" R.Pine S29E 45.9' "S16 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971