

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S <u>14</u> T <u>49N</u> R <u>10W</u>	_____	12
	S <u>14</u> T <u>49N</u> R <u>10W</u>	_____	6
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on 6 09/03/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (12-Sec. 14) South 1/16 corner, Section 14. Not established in the original survey.
- (6-Sec. 14) Northeast 1/16 corner, Section 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 14) Established the corner midway and on a straight line between Quarter corner 1317.37' south and the Center of Section 14 1317.37' north.
- (6-Sec. 14) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" Oak S11E 2.9' mrkd "S1/16 BT"
8" J.Pine N39W 21.7' do
6" J.Pine N01E 13.75' do
16" W.Pine N64E 44.45' do
Bearings are magnetic. | (6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" Maple S13W 1.89' mrkd "NE1/16 BT"
5" Maple N46W 3.68' do
13" W.Pine N84W 31.33' do
16" Oak S46W 10.7' do
Bearings are magnetic. |
|---|---|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/23/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

