

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<small>Luce</small>	<small>Located In:</small>	<small>Corner Code #</small>	
<small>(County)</small>			
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S 14 T 49N R 10W	J6	
	S 12 T 49N R 10W	3	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 08/20/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J6) Center of Section 14. Not established in the original survey.

(3-Sec. 12) North 1/16 corner between Sections 11 and 12. Not established in the original survey. 1972 - Established by Billy D. Buckler RLS midway and on line between Section and Quarter corners. Set 1" pipe with 4" aluminum cap. 12" R. Maple S80W 66.1', 18" R. Maple N18W 13.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(3-Sec. 12) Found, but did not accept the 1972 monument, in good condition. The 1972 position was fixed midway and on line between Section corner to north and a quarter corner position (K4) that Mr. Buckler had reestablished by proportionate measurement in 1972. The undersigned did not accept the 1972 1/4 corner and reestablished that corner in 2008. The position of the herein described 1/16 corner was consequently corrected and monumented midway and on the Section line between Section corner 1316.36' north and the 1/4 corner reestablished in 2008, 1316.36' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>(J6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 11" W.Pine S23W 18.2' mrkd "CS BT" 10" Cedar N32W 18.5' do 10" W.Pine N06E 7.35' do 5" Cedar N76E 14.3' do Bearings are magnetic.</p>	<p>(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 30" twin Maple N64E 8.4' mrkd "N1/16 BT" 17" Maple S74W 16.5' do 11" Maple N29W 35.95' do 16" Maple in clump N69W 55.15' do Bearings are magnetic. The 1972 monument was located S58E 16.2' distant and was destroyed.</p>
---	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/24/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

