

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<small>Luce</small>	<small>Located In:</small>	<small>Corner Code #</small>	
<small>(County)</small>			
1. Public Land Survey	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S 12 T 49N R 10W	_____	12
	S 12 T 49N R 10W	_____	L4
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/20/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(12-Sec. 12) South 1/16 corner, Section 12. Not established in the original survey.

(L4) Center of Section 12. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(12-Sec. 12) Established the corner midway and on a straight line between Quarter corner 1326.78' south and Center of Section 12 1326.78' north.

(L4) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" J.Pine N35E 17.25' mrkd "S1/16 BT"  
 9" J.Pine N78E 35.7' do  
 9" J.Pine S37E 24.78' do  
 10" J.Pine S08E 27.66' do  
 Bearings are magnetic.

(L4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 11" J.Pine N42W 22.85' mrkd "CS BT"  
 6" J.Pine N16E 16.79' do  
 5" W.Pine N39E 86.72' do  
 face of fence post S07E 17.14'  
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*  
 Surveyor's Michigan License No. 33986

Date 09/24/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

