

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S 12 T 49N R 10W		5
	S 12 T 49N R 10W		2
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 2 08/28/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 12) North 1/16 corner, Section 12. Not established in the original survey.

(2-Sec. 12) East 1/16 corner between Sections 1 and 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 12) Established the corner midway and on a straight line between Quarter corner 1320.27' north and Center of Section 12 1320.27' south.

(2-Sec. 12) Established the corner midway and on the Section line between Quarter corner 1311.21' west and Section corner 1311.21' east. The position for the corner falls on a steep slope.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" J.Pine S62E 2.54' mrkd "N1/16 BT"
 6" J.Pine S47W 3.13' do
 6" J.Pine N46E 6.42' do
 face of fence post S15E 20.05'
 Bearings are magnetic.

(2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" W.Pine N50W 8.35' mrkd "E1/16 BT"
 8" J.Pine S85E 4.7' do
 11" J.Pine S56E 21.35' do
 13" Oak clump S14E 33.75' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/24/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

