

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 14 T 49N R 10W	7
	S 14 T 49N R 10W	8
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 8 09/02/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 14) North 1/16 corner between Sections 13 and 14. Not established in the original survey.

(8-Sec. 14) West 1/16 corner, Section 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 14) Established the corner midway and on the Section line between Section corner 1318.73' north and Quarter corner 1318.73' south.

(8-Sec. 14) Established the corner midway and on a straight line between Quarter corner 1324.25' west and Center of Section 14 1324.25' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 10" W.Pine S20E 15.74' mrkd "N1/16 BT"  
 12" W.Pine S37E 32.28' do  
 5" Cedar S25W 16.56' do  
 5" W.Pine N14E 20.33' do  
 Bearings are magnetic.

(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 6" Cedar N56W 5.5' mrkd "W1/16 BT"  
 9" Cedar N40E 11.2' do  
 14" W.Pine S72E 25.5' do  
 10" W.Pine S39W 37.15' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/23/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities