

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
<small>(County)</small>		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 14 T 49N R 10W	2
	S 14 T 49N R 10W	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 14 08/28/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (2-Sec. 14) East 1/16 corner between Sections 11 and 14. Not established in the original survey.
- (14-Sec. 14) South 1/16 corner between Sections 13 and 14. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (2-Sec. 14) Established the corner midway and on the Section line between Quarter corner 1317.50' west and Section corner 1317.50' east. The position for the corner falls in the south shoulder of a snowmobile trail.
- (14-Sec. 14) Established the corner midway and on the Section line between Section corner 1319.68' south and Quarter corner 1319.68' north. The position for the corner falls in the center of a N-S fire lane.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"> (2) Set 5/8"x24" rebar with plastic MDNR cap. Set measuring nail with MDNR tag in the side of: 8" J.Pine S58E 9.6' mrkd "E1/16 BT" 8" J.Pine S61W 23.35' do 10" Maple N01E 26.05' do 16" W.Pine N67E 52.45' do Bearings are magnetic. | <ul style="list-style-type: none"> (14) Set a 5/8"x24" rebar with plastic MDNR cap below ground surface. Set measuring nail with MDNR tag in the side of: 12" R.Pine N27W 15.65' mrkd "S1/16 BT" 14" W.Pine N60E 46.65' do 6" J.Pine S55E 21.85' do 10" R.Pine S34W 15.7' do Bearings are magnetic. |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/23/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities