

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<small>(County)</small>	Located In:		Corner Code #	
1. Public Land Survey	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S 14	T 49N	R 10W	10
	S 14	T 49N	R 10W	3
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	
4. Lot No. _____, Recorded Plat _____				
5. Private Claims				

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(10-Sec. 14) South 1/16 corner between Sections 14 and 15. Not established in the original survey.

(3-Sec. 14) North 1/16 corner between Sections 14 and 15. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(10-Sec. 14) Established the corner midway and on the Section line between Section and Quarter corners 1319.77' south and north. The position for the corner falls on a steep west-facing slope (70% grade).

(3-Sec. 14) Established the corner midway and on the Section line between Section and Quarter corners 1319.77' north and south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 5" Maple N88W 12.95'      mrkd "S1/16 BT"  
 10" Balsam S06E 11.55'      do  
 6" Oak N35E 13.35'      do  
 5" Balsam N06E 9.75'      do  
 Bearings are magnetic.

(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" Maple clump N38W 2.15'      mrkd "N1/16 BT"  
 6" W.Pine S20E 28.7'      do  
 12" Spruce N59E 19.25'      do  
 7" Maple S78E 31.65'      do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/23/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities