

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 49N R 10W	I6
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 09/02/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I6) Quarter corner common to Sections 14 and 15. 1854 - Established by George Cannon Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Position monumented with a Witness Corner: "North between Sec. 14 & 15 ...35.10 Two Hearted River 75 links course ENE. Offset East 100 links thence N30'E 8.04 thence West 100 links and set post witness corner 3.14 North in line of Sections 14&15 left bank of stream. B.Ash 10" N58W 14 links, Elm 10" N10E 49 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I6) The original witness corner and accessories were not recovered. The witness corner position now falls in the meandering Two Hearted River. Reestablished the corner midway and on the Section line between Section corners 2639.55' north and south, being proportionate to the original record. The position for the corner falls in the Two Hearted River and cannot be monumented. Established a Witness Corner on the Section line 264.00' north of the corner position on the left bank of the River. The river bank is 17' south of the witness corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap 264.00' north of the corner position.  
 Set measuring nail with MDNR tag in the side of:  
 14" Balsam S75E 11.55' mrkd "WC NBT"  
 10" Balsam N29E 15.0' do  
 10" Balsam N50W 5.05' do  
 7" Balsam S46W 10.9' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/23/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities