

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>49N</u> R <u>10W</u>	<u>K6</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/31/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K6) Quarter corner common to Sections 13-14. 1854 - Established by George Cannon Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. W.Pine 14" S2 1/2E 180 links, Spruce Pine 8" N69W 283 links. 1958 - Remonumented by Billy D. Buckler RLS: "...as replaced by Marcus Schaaf, Registered Surveyor. Found 2" Iron pipe with W.Pine stump bottom bearing S2 1/2E, 180 links. Corner lies in N-S firelane". Set 1" pipe with 4" brass cap. 18" W.Pine S37E 42 links, 15" R.Pine N65W 60 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K6) Found the 1958 monument in good condition, adjacent to the 2" pipe of record, bent over. Accepted the 2" pipe as a careful and faithful perpetuation of the position of the original corner. Removed the bent 2" pipe and at its position, drove the 1958 monument flush to the ground. The corner lies in the east edge of a N-S firelane. The 1958 accessories are both in good condition and at record bearing and distance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K6) Fd. 1"IDx36" I.pipe with 4" brass MI Dept. of Conservation cap. Drove flush to ground. Set measuring nail with MDNR tag in the side of:
 27" W.Pine S29E 28.5' mrkd "1/4S" 1958 NBT
 23" R.Pine N59W 40.7' do do
 9" R.Pine S50W 25.57' mrkd "1/4S NBT"
 Red Pine N33E 9.8' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities