

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>10W</u>	<u>J7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/06/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J7) Quarter corner common to Sections 14 and 23. 1854 - Established by George Cannon Deputy Surveyor. Mr. Cannon calls for the "old" Qr. corner as describes it as being 40.17 chains S 89d30m W of Section corner thence 40.20 chains S 89d37m W to Section corner. Set post. W.Pine 24" N63E 30 links. Hemlock 10" S48W 10 links. 1952 - Remonumented by Dean C. DeLaMater RLS at a position located and perpetuated by Marcus Schaaf, Registered Land Surveyor. Remains of one original B.T. still in place, poor condition. Set 1" pipe with 4" brass cap. 12" Red Pine S87W 27 links, 12" Red Pine N83E 36 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J7) Found the 1952 monument in good condition, set inside a 2" ID iron pipe (Schaaf monument), at record bearing and distance from the 1952 accessories, both in good condition. Accepted same as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J7) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap in 2" ID Iron pipe. Set measuring nail with MDNR tag in the side of:
 16" R.Pine N89W 18.35' mrkd "1/4S" 1952 NBT
 16" R.Pine N81E 24.05' do do
 8" W.Pine N21E 19.0' mrkd "1/4S NBT"
 10" R.Pine S12E 19.5' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities