

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>49N</u> R <u>10W</u>	<u>15</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5								●					
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/06/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(15) Corner common to Sections 10-11-14-15. 1854 - Established by George Cannon Deputy Surveyor. Set post. Y. Birch 15" N29W 15 links, Y. Birch 24" S35E 45 links. 1958 - Remonumented by Billy D. Buckler RLS: "Replaced corner as set by Marcus Schaaf, Reg. Surveyor. Found 2" iron pipe with Yellow Birch BT N29W 15 links in good condition, tree dead but still standing." Set 1" pipe with 4" brass cap. 18" Cedar N41E 69 links, 13" Soft Maple S74W 27 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15) Found the 1958 monument in good condition, set inside a 2"ID Iron pipe (Schaaf monument), at record bearing and distance from the 1958 witnesses, both in good condition. The OBT Yellow Birch N29W 15 links is in place, now a rotted stump. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap, set inside a 2"ID I.pipe.
 Set measuring nail with MDNR tag in the side of:
 22" Cedar N41E 46.2' mrkd "S11" 1958 NBT
 16" Maple S81W 18.2' "S15" do
 6" Maple N40W 15.25' mrkd "S10 NBT"
 6" Maple S12W 14.85' "S12 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/23/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities