

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>10W</u>	<u>K7</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 08/14/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(K7) Corner common to Sections 13-14-23-24. 1854 - Established by George Cannon Deputy Surveyor. Witnesses: Beech 10" S36E 18 links, Beech 10 N60W 30 links. Corner likely remonumented by Marcus Schaaf sometime prior to his retirement in 1949. 1958 - Remonumented by Billy D. Buckler RLS: "Replaced from testimony of B. McTiver, District Forester, in intersection of N-S-E-W firelanes. Pipe has been removed by vehicle traffic. Set 1" pipe with 4" brass cap. 14" R.Pine N51W 107 links, 17" R.Pine N34E 71.5 links, 17" W.Pine S10E 32 links." The pipe referred to by Mr. Buckler was undoubtedly that placed by Schaaf and subsequently testified to by Mr. McTiver.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K7) The 1958 monument was not recovered. Found a 2" iron pipe underground and bent over, likely that placed by Marcus Schaaf and undiscovered by Billy Buckler. I accepted the position of the 2" pipe as the best available evidence of the position of the original corner. Removed the pipe and drove a new monument. The 1958 witnesses were all recovered in good condition. From them, the 1958 position of record is N25E 3 feet distant from the position monumented. The position for the corner falls east of intersection of firelines N-S-W (firelane appears to curve around the corner position).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K7) Set 1"ID I.pipe with plastic MDNR cap flush with ground at position of fd. 2" pipe. Set measuring nail with MDNR tag in the side of:  
 26" W.Pine S05E 18.6' mrkd "S24" (1958 NBT)  
 16" R.Pine N49W 73.95' old marks do  
 18" R.Pine N26E 49.75' mrkd "S13" do  
 7" R.Pine N70E 24.05' mrkd "S13 NBT"  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/23/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities