

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>10W</u>	<u>17</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 08/05/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I7) Corner common to Sections 14-15-22-23. 1854 - Established by George Cannon Deputy Surveyor. Set post. Balsam 6" S75W 16 links, Aspen 5" N10E 41 links. 1952 - Remonumented by Dean C. DeLaMater RLS at position previously located and perpetuated by Marcus Schaaf, RLS. Set 1" pipe with 4" brass cap. 10" Red Pine N46W 63 links, 18" W.Pine N76E 62 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I7) Found the 1952 monument in good condition set inside a 2" ID iron pipe (Schaaf monument), at record bearing and distance from the 1952 witnesses, both in good condition. Accepted same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I7) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap inside 2" ID Iron pipe. Set measuring nail with MDNR tag in the side of:
 22" W.Pine N77E 41.55' mrkd "S14" 1952 NBT
 18" R.Pine N37W 42.1' "S15" do
 14" W.Pine N01E 35.95' mrkd "S14 NBT"
 8" W.Pine S13W 14.1' "S23 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/23/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities