

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>10W</u>	<u>L5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 08/04/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L5) Quarter Corner common to Sections 12-13. 1854 - Established by George Cannon Deputy Surveyor midway and on the Section line between Section corners 39.81 chains east and west. Set post. Sp. Pine 6" S84E 13 links, Sp. Pine 7" N20W 31 links. 1958 - Corner remonumented by Billy D. Buckler at position "set by Marcus Schaaf, Reg. Surveyor. Found Iron Pipe buried in E-W fireline". Set 1" pipe with 4" brass cap. 6" J.Pine N22E 17 links, 7" J.Pine S34E 19 links. 1991 - Gerald L. Wiggins RLS found the 1958 monument bent and remonumented the position with a 1" pipe with plastic RLS cap. 12" J.Pine S67W 26.5', 10" J.Pine N34W 12.6', 6" J.Pine N22E 11.22', 7" J.Pine S34E 12.54'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L5) The original post and accessories were not recovered. Found the 1991 monument in good condition and at record bearing and distance from two of the four 1991 accessories. The Jack Pine NBTs NE and SE were found in good condition. The Jack Pine NBTs SW and NW were not recovered. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L5) Found 1" ID I.pipe with plastic MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" J.Pine N26E 11.5' open blazes (1991 NBT)
 10" J.Pine S29E 13.15' do do
 10" J.Pine S55W 46.15' mrkd "1/4S NBT"
 9" J.Pine N72E 36.6' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/24/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities