

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>49N</u> R <u>10W</u>	<u>L3</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 07/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(L3) Quarter corner common to Sections 1 and 12. 1854 - Established by George Cannon Deputy Surveyor midway and on the Section line between Section corners 39.99 chains east and west. Set post. Sp. Pine 10" N85E 90 links, Sp. Pine 10" S30W 18 links. Note: stated bearings are labelled "old bearings" in the copy of the GLO notes in possession of the undersigned. 1957 - Corner rewitnessed by Billy D. Buckler RLS "as perpetuated by Marcus Schaff, Reg. Surveyor. 1/4 corner is 2" iron pipe in concrete buried in center of E-W firelane. Found pits and mounds made by Schaff, NW and SE of 1/4 corner". Witnesses: 10" Jackpine S25E 60 links, 7" Jackpine N24E 49 links. 1976-1977 Billy D. Buckler again rewitnessed the 2" pipe monument (record dated 1984): 10" J.Pine S79W 55.8', 5" Maple S24W 43.8'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L3) The original post and accessories were not recovered. Found the 2" iron pipe of record, in good condition, and at record bearing and distance from the NBTs described in the 1984 record, both in good condition. The 5" Maple S24W, however, is actually an Oak. Accepted the monument as the best available evidence of the position of the original corner and drove a 5/8"x24" capped rebar into the center of the pipe.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L3) Set 5/8"x24" rebar with plastic MDNR cap in found 2"ID iron pipe.  
 Set measuring nail with MDNR tag in the side of:  
 12" J.Pine S82W 56.2' mrkd "1/4S" Buckler NBT  
 8" Oak S27W 43.8' do do  
 5" J.Pine S65E 32.05' mrkd "1/4S NBT"  
 6" twin J.Pine N55W 16.35' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/24/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities