

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 10W	K5
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

(K5) Corner common to Sections 11-12-13-14. 1854 - Established by George Cannon Deputy Surveyor. Set post. Sp. Pine 6" N51E 48 links, Sp. Pine 6" S65W 29.5 links. 1958 - Billy D. Buckler RLS found 2" iron pipe set by Marcus Schaaf, Reg. Surveyor, in intersection of firelanes. Found no evidence of Jack Pine B.T.s. Set 1" pipe with 4" brass cap. 18" W.Pine S37E 67 links, 18" W.Pine N60W 93 links. 1985 - 1958 monument recovered by Gerald L. Wiggins RLS, who made new witnesses: 26" W.Pine N57W 61.1', 8" W.Pine N45E 23.7', 10" R.Pine S70E 28.0', 12" W.Pine S20W 20.2'. Mr. Wiggins corner record, dated Sept. 10 1986, improperly references and describes the history of K5 T49N-R09W. Only Part C of the 1986 LCRC applies to this corner.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K5) The original post and accessories were not recovered. the 1958 monument was not recovered. Found the Schaaf monument, a 2"ID iron pipe, in good condition and at record bearing and distance from all of the 1985 witnesses, one of them being the same W.Pine NBT (N60W 93 links) described in the 1958 record, all in good condition. Accepted the 2" pipe as the best available evidence of the position of the original corner and replaced it with a 1"ID capped iron pipe set flush with the ground. The position for the corner falls in the intersection of firelanes N-S-W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K5) Set 1"IDx36" I.pipe with plastic MDNR cap. Set measuring nail with MDNR tag in the side of:  
 29" W.Pine N64W 60.72' mrkd "S11" 1985 NBT  
 16" R.Pine S64E 28.6' "S13" do  
 15" W.Pine S24W 20.9' "S14" do  
 11" W.Pine N49E 24.21' "S12" do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 09/24/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities