

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. S., R. 11 E. W.	K-3A
2. PROPERTY CONTROLLING IN SECTION	T. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David F. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-19, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-3A Meander corner on the North section line of Section 11. O.L.T.'S. Wood Post, W. Pine 15", N63°W, 15 lks. and W. Pine 7", S36°W, 31½ lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-3A Set at G.L.O. record distance (706.2') East of the North 1/4 corner of section 11, and with a deflection of 43 minutes North from a line between said North 1/4 corner and the N.W. section corner of section 11: As recorded in the notes of the original Gov't Survey. This position causes the Meander Lines of Muskegon Lake to fit the Lake Shore very well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3A D.N.R. Monument. New Bearings: 10" J. Pine, S2°W, 67.37' & 16" W. Pine, S87°W, 106.94' & 10" W. Birch, S76°W, 18.73' & 8" W. Birch, N35°E, 21.10' & 1½" pipe, N12°W, 38.12'. Corner lies 46' West of lake edge.

SIGNED BY

*David F. Babbitt*

DATE 3-3-83

David F. Babbitt

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY

CHIEF OF SURVEY PARTY

DATE

APPROVED AND SIGNED BY

MICHIGAN REGISTERED LAND SURVEYOR

DATE