

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 49 N.R. 11 W


       Twp        COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 10-11

CORNER MONUMENT 1" Pine with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 5/8/63 (Corner moved 9/8/65)

WITNESSES TO CORNER..... 6" W. Pine (1/4S NBT), N 66° W, 03 1/2 Lks.



10" Red Pine (1/4S NBT), N 60° E, 38 1/2 Lks.

18" Red Pine (1/4S NBT), S 7° W, 75 1/2 Lks.

AND

CIRCLE CORNER REGISTERED

### DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established 18.6 links East of a straight line and by Proportional distance between two Section Corners. No evidence of Original Corner.

SURVEYOR'S SEAL

*Billy D. Buckler*

SIGNED

Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 2/24/1966