

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 N. R. 11W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to sections 16-17-20-21

CORNER MONUMENT 2" Iron Pipe buried 12" deep in intersection of N-S Fire line and Grand Marais road.

DATE MONUMENT PLACED AND WITNESSED 7-26-61

WITNESSES TO CORNER..... 12" Red Pine (S17 NBT) N18°W 89 links



Trees marked by unknown surveyor
11" Red Pine S36°W 51½ links

15" Red Pine S36°E 76 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-witnessed as set by unknown surveyor. Found 2" Iron Pipe in concrete buried. Placed 3/8" Iron Bar beside pipe.
No evidence of original witnesses.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 30, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler