

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 11 W.

Luce COUNTY

DESCRIPTION OF CORNER Section corner common to Section 29, 30, 31, and 32.

DESCRIPTION OF CORNER MONUMENT 2" X 48" Iron Pipe buried in intersection of
N-S-E-W firelane.

WITNESSES TO CORNER 15" W. Pine N 75 E 103 1/2 Links (S 29 MBT)

12" W. Pine N 28 W 115 Links (S 30 MBT)

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was replaced from Y. Pine B.T. bearing N 81 E, 38 Links. B.T. is stub
in fair condition.

Shown by McTiver, District Forester.

Corner placed and witnessed on 10 June 1958.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 5-23-59
REGISTERED LAND SURVEYOR