

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 NR. 11 W.

----- Luce ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 7, 8, 17 and 18.

DESCRIPTION OF CORNER MONUMENT 1/2" X 3/8" Iron Bar.

WITNESSES TO CORNER 16" Hemlock S 30 W 62 Links, Marked "S 18 BPT"

14" Hemlock S 62 E 29 Links, Marked "S 17 BPT"

10" Red Pine N 74 W 72 Links, Marked "S 7 BPT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from one Beech B.T. bearing N 55 E, 13 Links. Tree green but rotted in center.

Found discoloration in soil from Iron Pipe which has been removed.

Corner lies in intersection of N-S-E-W firelanes.

Corner was placed and witnessed with B. McTiver, District Forester, on 26 May 1958.

SURVEYORS SEAL

SIGNED

Billy D. Buckler

Billy D. Buckler

DATE 5-19-59

REGISTERED LAND SURVEYOR