

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 N.R. 11W


Ince COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 31 and 32.

CORNER MONUMENT 1" Pipe with 4" Brass Cap, buried in N.-S. Fire lane.

DATE MONUMENT PLACED AND WITNESSED 7-8-63 with George Hamilton, Ass't.

WITNESSES TO CORNER..... 10" Red Pine (1/4 S. N.B.T.) N. 72° E., 34 1/2 lks.



8" Jack Pine (1/4 S. N.B.T.) S. 72° W., 50 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by single proportionate measure between two Sec. Cors. and on North-South Fire line.

No evidence of Original Cor.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4/27/64
REGISTERED LAND SURVEYOR